

TEMPORARY HOLD DOWN STRAPS

STEEL CROSS-BROKEN LID

STEEL CAP FLASHING

NON-INSULATED STEEL CURB MOUNTED FRAME

MANUAL RELEASE HANDLE

DOME HINGE (3 PER DOOR)

INSULATION

90°

STRIKER BRACKET

LOCK OPEN ARM

SHOCK ABSORBER

FOAM GASKET

CONDENSATION GUTTER

LATCH ASSEMBLY

12" BOTTOM OF FRAME TO HINGE POINT

ALUM. CHANNEL

SPRING HOUSING

INSIDE MANUAL RELEASE CABLE

ROUGH OPENING DIMENSION

*FUSIBLE LINK TEMP: PLEASE SELECT ONE:
165° ○ 212° ○ 286° ○ 360° ○

MODEL : SVSM-CM

SCALE : NTS

BRISTOL CURB MOUNTED SMOKE VENT w/METAL LIDS



MODEL SIZE	ROUGH OPENING DIMENSION	QTY
4848	48" x 48"	
6060	60" x 60"	
4872	48" x 72"	
6072	60" x 72"	
4896	48" x 96"	
6096	60" x 96"	

NOTES:

- CORROSION RESISTANT CONSTRUCTION IS USED THROUGHOUT THE UNIT.
- FRAME MATERIAL IS 14ga. GALVANIZED STEEL
- GASKETED DOORS ARE CROSS-BROKEN METAL LIDS
- DOORS WILL OPEN AGAINST 10 LB. PER SQ.FT. SNOW OR WIND LOAD.
- "STAR" FUSIBLE LINK AVAILABLE IN FOLLOWING: 165°, 212°, 286°, 360°. UNLESS OTHERWISE REQUESTED, 165° WILL BE SUPPLIED.
- DOORS WILL RESIST AN UPLIFT PRESSURE OF 30 LBS. PER SQ.FT., 40 PSF DOWN LOAD.
- ANCHOR FASTENERS ARE BY THE INSTALLING CONTRACTOR.
- UNITS EQUIPPED W/ BOTH OUTSIDE & INSIDE MANUAL RELEASES.
- CURB MOUNTED - (INSULATED FRAME OPTIONAL)

Bristolite® Daylighting Systems

401 East Goetz Avenue, Santa Ana, CA. 92707
TEL 714.540.8950 / FAX 714.540.5415

CUSTOMER :

PREPARED BY :

JOB NO :

PROJECT :

SUBMITTAL DATE :

ARCHITECT :